



Alaska Rim Engineering Inc.  
 9131 E. Frontage Road  
 Palmer, AK 99645  
 907-745-0222

*Paid # 4265*

Dale, John  
 13839 W. Lotus Dr  
 Big Lake, AK 99652

Invoice number 17-00360  
 Date 06/08/2017

Project 17-00360 BIG LAKE HEIGHTS #1 B7 L7

REMIT PAYMENTS TO: 9131 E. FRONTAGE RD. PALMER, AK 99645

Description	Contract Amount	Prior Billed	Current Billed
PACKAGE #1			
TRAVEL	349.00	0.00	349.00
	50.00	0.00	50.00
Total	399.00	0.00	399.00

Invoice total 399.00

**Aging Summary**

Invoice Number	Invoice Date	Outstanding	Current	Over 30	Over 60	Over 90	Over 120
17-00360	06/08/2017	399.00	399.00				
	Total	399.00	399.00	0.00	0.00	0.00	0.00

*Invoices are due and payable in full upon receipt. Finance charges of 1.5% per month (18% APR) will be assessed on all past due amounts. If this invoice is referred for collection, all associated costs, fees, and charges are the responsibility of the invoiced client and will be added to the total balance due. This disclosure is provided in accordance with applicable statute.*



ON-SITE  
WATER AND WASTEWATER DISPOSAL SYSTEMS  
ENGINEER'S EVALUATION

PROPERTY DESCRIPTION:  
SITE ADDRESS: Big Lake Heights #1 B7 L7  
13839 W. Lotus Dr.  
Big Lake, AK 99652

This property is developed to serve a single family residence with a total of two (2) bedrooms.

Applicant Name: John Dale  
Applicant Address: 13839 W. Lotus Dr.  
Big Lake, AK 99652

ON-SITE DRINKING WATER SYSTEM:

- This property is served by a Public Water System, approved by ADEC and currently in monitoring compliance.
- A recent drinking water sample was tested at an ADEC certified laboratory and was found to meet current ADEC drinking water standards for total coliform bacteria.

NOTES:

ON-SITE WASTEWATER DISPOSAL SYSTEM:

- A new wastewater disposal system has been installed. Refer to the enclosed data.
- This wastewater disposal system was installed by an ADEC Certified Installer and is on file at ADEC.
- The existing wastewater disposal system was tested in accordance with current ADEC policy and the readily identifiable features of this system were observed and documented. The system was found to be operating satisfactorily.
- It appears this system meets 18 AAC 72 regulations and ADEC policies of the time it was installed.
- This system is documented with ADEC.

NOTES: The monitor tube is mostly filled in, the monitor tube needs repaired/replaced as well it needs a water tight cap.

*This report does not constitute a guarantee of any kind, explicit or implied, as to the future performance of this water supply or wastewater disposal system. It does accurately portray the conditions found on the date they were tested and/or documented. This approval does not imply the wastewater system is free of material or installation defects and/or possible subsequent failure.*

Sincerely,  
Alaska Rim Engineering, Inc.



June 8, 2017

cc: ADEC

AK Rim File No. 17 -00360

**DOCUMENTATION  
OF  
AN ON-SITE WATER SUPPLY SYSTEM  
AND  
WASTEWATER DISPOSAL SYSTEM**


<b>I. GENERAL INFORMATION</b>		AK Rim File No. 17-00360
Legal Description of the Location <b>Big Lake Heights #1 B7 L7 13839 W. Lotus Dr.</b>		
Applicant Name <b>John Dale</b>	Applicant is: (Check one) <input checked="" type="checkbox"/> Owner Builder <input type="checkbox"/> Certified Installer <input type="checkbox"/> Engineer <input type="checkbox"/> Bank	
Mailing Address <b>13839 W. Lotus Dr.</b>	Type of Residence: <input checked="" type="checkbox"/> Single-Family <input type="checkbox"/> Multi-Family <input type="checkbox"/> Duplex	Total Number of Bedrooms <b>2</b>
City, State and Zip Code <b>Big Lake, AK 99652</b>	Telephone <b>907-232-9249</b>	

<b>II. WATER SUPPLY SYSTEM</b>					
Source of Water and Containment: (Check all that Apply) <input checked="" type="checkbox"/> Well (Drilled or Driven) <input type="checkbox"/> Surface (Identify) <input type="checkbox"/> Roof Catchment <input type="checkbox"/> Other (Identify) <input type="checkbox"/> Holding Tank		Type of Water Supply System: <input checked="" type="checkbox"/> Private <input type="checkbox"/> Public (Serves more than one family)		Treatment of Water: (Check all that Apply) <input checked="" type="checkbox"/> None Known <input type="checkbox"/> Chlorination <input type="checkbox"/> Filtration <input type="checkbox"/> Mineral Removal <input type="checkbox"/> Other	
(1)		(1)		(1)	
Well Data:					
Is the height of the well casing more than 12" above the ground?				<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	(1)
Is a sanitary seal or well cap installed on the well casing?				<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	(1)
Is drainage directed away from or around the casing within a radius of 10 feet from the well casing?				<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No	(1)
Is well wire enclosed in conduit?				<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	(1)
Date Drilled <b>unknown</b>	Depth of Well: (Feet) <b>unknown</b>	Static Water Level: (Feet) <b>22.2</b>	Yield: (Gal/Min) (If available) <b>unknown</b>	Pump Rate: (Gal/Min) (If available) <b>6.4</b>	
(2)	(2)	(1)	(2)	(1)	
Separation Distances from the Well Casing to each of the Following Sources of Contamination:					
Septic Holding Tank on Lot: <b>&gt; 100 feet</b>		Sewer Lines on Lot: <b>&gt; 25 feet</b>		Absorption Area on Lot: <b>&gt; 100 feet</b>	
(1)	(1)	(1)	(1)	(1)	
Closest Septic Holding Tank on Adjacent Lot: <b>&gt; 100 feet</b>		Closest Sewer Lines on Adjacent Lot: <b>&gt; 25 feet</b>		Closest Edge of Absorption Area on Adjacent Lot: <b>&gt; 100 feet</b>	
(1)	(1)	(1)		(1)	
If toxic materials are stored on the property, including fuel tanks, paints, lubricants and other petroleum based materials, pesticides, fungicides or herbicides, indicate distance from contaminants to well casing:			On Lot: <b>none known &lt;25'</b>	On Adjacent Lot: <b>none known &lt;25'</b>	
			(1)	(1)	
Water Sample Taken By: (Name) <b>Kaley Lyles, Alaska Rim Engineering, Inc.</b>				Sampler is: <input type="checkbox"/> Buyer <input checked="" type="checkbox"/> Engineer Tec.	
Address: <b>9131 E Frontage Rd. Palmer, AK 99645</b>				<input type="checkbox"/> Banker <input type="checkbox"/> Government Official	
Water Sample Results: (Attach Copy) <input checked="" type="checkbox"/> Satisfactory - Date <b>6/7/2017</b> <input type="checkbox"/> Unsatisfactory - Date:					
<b>Comments / Recommendations:</b> <u>Data Legend</u> (1) From site visit on 6/7/17 (2) From ADEC records (3) From well cap (4) (5)					

## DOCUMENTATION OF ON-SITE WATER AND WASTEWATER DISPOSAL SYSTEMS

<b>III. WASTEWATER DISPOSAL</b>		Legal Description: <b>Big Lake Heights #1 B7 L7</b>			
<input checked="" type="checkbox"/> Septic Tank Absorption System		<input type="checkbox"/> Package Treatment (Specify Brand Name or Process):			
<input type="checkbox"/> Holding Tank (Specify)	Capacity of Tank:	Where Waste is Disposed:		Frequency of Pumping:	
<input checked="" type="checkbox"/> Septic Tank Outfall Discharged To <b>On-Site Soil Absorption System</b>		<input type="checkbox"/> Other (Specify - Outhouse, Incinerator, etc.)			
<input type="checkbox"/> <b>NEW SYSTEM</b>					
Name of Installer:					Date Installed:
<input type="checkbox"/> Owner Builder:	<input type="checkbox"/> Certified Installer No.:	<input type="checkbox"/> Other:	Septic Tank Type / Manufacturer:		
Septic Tank Size (Gallons):		Number of Compartments:		Soil Type and Rating:	
Type Soil Absorption System:		Dimensions - Size Soil Absorption System:		Type Quantity Distribution Rock Used for Soil Absorption System:	
Percolation Test Results: (Attach Copy of Report)		Percolation Test by: (Name)			
Minimum Ground Cover over Absorption Area:		Minimum Ground Cover over Septic Tank:		Cleanout Pipes / Caps Installed on Septic Tank:	
Separation Distance To:		Water Supply Source on Lot:		Nearest Water Supply Source on Adjacent Lot:	
Nearest Body of Water:		Water Table / Bedrock:		Lot Line:	
Comments / Recommendations:					

<input checked="" type="checkbox"/> <b>EXISTING SYSTEM</b>					
Name of Installer:					Date Installed:
<b>Mike Alexander</b>					(2)
<input type="checkbox"/> Owner Builder:	<input type="checkbox"/> Certified Installer No.:	<input checked="" type="checkbox"/> Other:	Septic Tank Type Manufacturer:		
Septic Tank Size (Gallons):		Number of Compartments:		Soil Type and Rating:	
1000		2 (2)		HDPE/WEDCO Canada (2)	
Type Soil Absorption System:		Dimensions - Size Soil Absorption System:		Type Quantity of Distribution Rock Used for Absorption System:	
deep trench (2)		30'x5' (2)		3/4" - 3" sewer rock / 22 cu. yds. (2)	
Adequacy Test Results: (Attach Copy)		Adequacy Test Performed By: (Name)			
<input checked="" type="checkbox"/> Pass <input type="checkbox"/> Fail (6/7/2017) (1)		Vincent Cobler, AK Rim Engr., Inc. (1)			
Min. Ground Cover over Absorption Area:		Min. Ground Cover over Septic Tank:		Does the septic tank require pumping:	
unknown (3)		45" (3)		<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No (1)	
Separation Distance To:		Nearest Water Supply Source on Adjacent Lot:		Nearest Body of Water:	
>100 Feet (1)		>100 Feet (1)		>100 Feet (1)	
Water Supply Source on Lot:		Cleanout Pipes Caps Installed on Septic Tank:		Cleanout Pipes Caps Installed on Absorption System:	
		<input checked="" type="checkbox"/> Yes <input type="checkbox"/> No (1)		<input type="checkbox"/> Yes <input checked="" type="checkbox"/> No (1)	
Water Table / Bedrock:		Lot Line:			
>4' / >6' (2)		>10' (2)			
<p><b>Comments / Recommendations:</b> A cleanout is located <input type="checkbox"/> inside <input checked="" type="checkbox"/> outside the foundation.</p> <p><u>Data Legend</u></p> <p>(1) From site visit on 6/7/17                  (2) From ADEC records                  (3) Cover estimated from site conditions</p> <p><b>Note:</b> The monitor tube is mostly filled in, the monitor tube needs repaired/replaced as well it needs a water tight</p>					

The information in sections I, II, and III is correct to the best of my knowledge.	
Signature:	Typed Printed Name:
	Norman K. Gutcher
Date:	Reg. No.:
6/8/17	CE 4919

*This documentation does not constitute a guarantee of any kind, explicit or implied, as to future performance of this water supply or wastewater disposal system. It does accurately portray the conditions found on the date they were tested and/or documented.*





# Mat-Su Test Lab, LLC



Midtown Community Business Park  
9161 East Frontage Road, Suite 15  
Palmer, Alaska 99645  
Phone: 745-3005 / Fax: 745-3010  
Website: [www.mstl.biz](http://www.mstl.biz) E-Mail: [mstl@mstl.biz](mailto:mstl@mstl.biz)

## Drinking Water Analysis Report Total Coliform Bacteria (SM9223B by Colilert)

*See Reverse Side For Instructions*

Client: <u>AK-R.M 17-360</u>	
Mailing Address:	PWSID# (if applicable):
Phone #:	Fax # or E-mail:

Legal Description of Property: Big Lake Heights #1 B7L7

Sample Site Location: OHB Deliverer Initials: KL  
(I.E.: bathroom sink, outside hose bib)

Date Sampled: 6/6/17 Time Sampled: 1:28pm Sampler Initials: KL

Circle One: Standard Test (\$42) / Rush Test (\$52)

Circle One: Routine Test / Repeat Test / Special Purpose

### This Section to Be Completed by Lab

#### Analysis Results:

Lab ID # AR 17172

- Satisfactory
- Unsatisfactory
- Sample Rejected - Reason: \_\_\_\_\_

#### Chromogenic/Fluorogenic Method Results:

A Total Coliform Present (P)/Absent (A) ( Yellow / No Color )

A E. Coli Present (P)/Absent (A) ( Fluorescence / No Fluorescence )

Incubator # 1

	Received :	JUN 06 2017	15:37	By: <u>AS</u>
	Started :	JUN 06 2017	15:44	By: <u>AS</u>
	Finished :	JUN 07 2017	1550	By: <u>CW</u>

"Tracy"  
**SHAMROCK SEPTIC INC.**

shamrockseptic.net / clover@mtaonline.net

**PUMPER'S OPINION**

Location 13837 W Lotus  
DATE PUMPED 7/22/17

**YOUR SERVICE TECHNICIAN**

SERVICE TECH \_\_\_\_\_

HOUSEHOLD TREATMENT      A B C D F  
SYSTEM CONDITION      A B C D F

This report is to give you a better insight on your system and what you may do to make it last longer or cure any problems that exist or may become a problem in the future.

**SUGGESTIONS**

Re-pump in \_\_\_ months 3 years  Add bacteria  Repair leach field  Replace tank  Repair mainline clean out tube  Replace outflow pipe  Switch to liquid laundry soap  Stop entry of grease into system  Change toilet paper brand  Repair leaking faucet  Conserve on water  Laundry water should not be run into septic  Clean vents on roof  Replace or install caps on septic pipes  Repair broken pipes  Have main line drain cleaned  Space out high volume usage over day or week (laundry, baths)  Have main line scoped w/video camera  Increase maintenance schedule

**TANK TYPE**

METAL  CONCRETE  FIBERGLASS  PLASTIC  LOG CRIB  OTHER  CAN'T DETERMINE  
 1000 GAL  1250 GAL  1500  1750  2000  2250  2500  OTHER \_\_\_\_\_

**LEACH FIELD TYPE**

TRENCH  BED  LEACH TANK  RAISED FIELD W/LIFT STATION  CRIB  CAN'T DETERMINE  N/A

**SOLID CONTENT**

Light  Acceptable  Heavy  Extremely Heavy  Abused

**BACTERIA**

Little to no action  Good  Excellent

**ABUSE NOTED**

Each of these will cause main line backups and/or leach field failure

None noted  Grease or powdered laundry detergent  Paper towels  Wipes  Feminine hygiene products  Excessive amounts of paper products  Lack of maintenance

**LEACH FIELD**

Excellent  Good  Fair  Poor  Saturated  Extremely saturated

Could not locate monitor tube, but system seems adequate for usage it is receiving at this time

If your leach field is saturated, it means that it is not accepting all the water that is being used at this time. Causes could be as simple as extra guests, large party, or a leaking faucet.

Ground water, at certain times such as spring break up and heavy rains, can affect the field in bad soils and low-lying areas.

It could also mean that your leach field is starting to fail and repairs will have to be made to system. If that is the case, start-putting money away to have it dug up and repaired. There is no chemical or any other method that we recommend to cure a bad leach.

By pumping your system, you will stop solids that will bypass the baffles (due to the tank being over full) and contaminate the field. Pumping will also give your system time to rest and dry up but during this time, remember water is your systems enemy and should be used sparingly.

On a failed system, pumping may only be a temporary cure. You could go trouble free for a year, or you could be calling us back in a couple of days.

**TANK / LEVELS & CONDITION**



Normal  Below normal  Above normal  
 Has been over full in past  Tank rusting out see #  4  5  6 or  leach field  
 Old & coming to end of life expectancy  Tank has cracks  Tank collapsed  In need of repair


**OTHER PROBLEMS:**

None noted  Parted main line clean out  Plugged out flow pipe  Plugged inlet baffle  
see #  1  2  3  4  5  7  
 Tank has holes due to rust (may collapse)  Center baffle has fallen (keep up with maintenance)

# Report for On-Site Water and Sewer System Certification

<b>III. WASTEWATER DISPOSAL</b>					
<input type="checkbox"/> Septic Tank/Absorption System			<input type="checkbox"/> Package Treatment: (Specify Brand Name or Process)		
<input type="checkbox"/> Holding Tank - Specify:	Capacity of Tank	Where Waste is Disposed		Frequency holding tank pumped	
<input type="checkbox"/> Septic Tank Outfall Discharged To:			<input type="checkbox"/> Other (Specify): (Outhouse, Incinerator, etc.)		
<input checked="" type="checkbox"/> <b>New System Project #95085 L7/B7 Big Lake Heights #1</b>					
Name of Installer <b>Mike Alexander</b>					Date Installed <b>6-6-95</b>
<input type="checkbox"/> Owner/Builder		<input type="checkbox"/> Installer No. _____		<input checked="" type="checkbox"/> Other: <b>contractor</b>	
Septic Tank Size (Gallons) <b>1,000</b>		Number of Compartments <b>2</b>		Type/Manufacturer <b>HDPE/WEDCO Canada</b>	
Type Soil Absorption System <b>DEEP TRENCH</b>		Dimensions/Size Soil Absorption System <b>30' Long x 5' E. Depth</b>		Type/Quantity Backfill Material used for Soil Absorption System <b>Approx. 22 CYD 3/4-3" S.ROCK</b>	
Percolation Test Results <b>N/A</b>		Percolation Test by: (Name)			
Minimum Ground Cover over Absorption area <b>4</b> Feet		Minimum Ground Cover over Septic Tank <b>4</b> Feet		Cleanout Pipes/Caps Installed on Septic Tank <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No	
Cleanout Pipes/Caps Installed on Absorption System <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No		Separation Distance to: <b>+100</b> Feet		Nearest Water Supply Source on Adjacent Lot <b>+100</b> Feet	
Nearest Body of Water <b>+100</b> Feet		Water Table/Bedrock <b>+4/6</b> Feet		Lot Line <b>+10</b> Feet	
Comments/Recommendations  <p style="text-align: center;">A representative of Erdman &amp; Associates logged a test hole, designed and inspected construction of the septic system. ADEC approved the HDPE plastic septic tank.</p>					

<input type="checkbox"/> <b>Existing System</b>					
Name of Installer					Date Installed
<input type="checkbox"/> Owner/Builder		<input type="checkbox"/> Installer No. _____		<input type="checkbox"/> Other:	
Septic Tank Size (Gallons)		Number of Compartments		Type/Manufacturer	
Septic Tank Size (Gallons)		Number of Compartments		Soil Type or Rating	
Type Soil Absorption System		Dimensions/Size Soil Absorption System		Type/Quantity Backfill Material used for Soil Absorption System	
Adequacy Test Results: <input type="checkbox"/> Pass <input type="checkbox"/> Fail		Adequacy Test Performed By: (Attach Copy of Report)		Date Septic Tank Summed (Attach Copy of Receipt)	
Minimum Ground Cover over Absorption Area Feet		Minimum Ground Cover over Septic Tank Feet		Cleanout Pipes/Caps Installed on Septic Tank <input type="checkbox"/> Yes <input type="checkbox"/> No	
Cleanout Pipes/Caps Installed on Absorption System <input type="checkbox"/> Yes <input type="checkbox"/> No		Separation Distance to: Feet		Nearest Water Supply Source on Adjacent Lot Feet	
Nearest Body of Water Feet		Water Table/Bedrock Feet		Lot Line Feet	
Comments/Recommendations					
					
I certify that the above information is correct:					
Signature 		Typed/Printed Name <b>Michael R. Erdman</b>		Title, Reg./Cert. No., Inst. No. <b>CE-4252</b>	
				Date <b>8/10/95</b>	
NOTE: Must be signed by a professional engineer.					



# Report for On-Site Water and Sewer System Certification

# RECEIVED

AUG 15 1995  
Audit Stamp No. \_\_\_\_\_

DEPARTMENT OF ENVIRONMENTAL CONSERVATION  
MS90

<b>I. GENERAL INFORMATION</b>			
Legal Description of the Location  <p style="text-align: center;">Lot 7 Block 7 Big Lake Heights Addition #1</p>			
Applicant Name <p style="text-align: center;">Barbara Shaw</p>		Applicant is: (Check one) <input type="checkbox"/> Bank <input type="checkbox"/> Installer <input checked="" type="checkbox"/> Owner/Builder	
Address (Street or P. O. Box) <p style="text-align: center;">P.O. Box 520466</p>		Type of Residence <input checked="" type="checkbox"/> Single Family <input type="checkbox"/> Multi-Family	Total No. of Bedrooms <p style="text-align: center;">2</p>
City, State and Zip Code <p style="text-align: center;">Big Lake, AK 99652</p>		Telephone <p style="text-align: center;">892-7572</p>	Public Accommodation: <input type="checkbox"/> Restaurant <input type="checkbox"/> Lounge <input type="checkbox"/> Other
Send Approval to: <input type="checkbox"/> Applicant <input type="checkbox"/> Other: (Give Name & Address)			

<b>II. WATER SUPPLY SYSTEM</b> <span style="float: right;">Not requested at this time</span>				
Source of Water and Containment (Check all that Apply)		Type of Water Supply System		Treatment of Water (Check all that Apply)
<input type="checkbox"/> Well (Drilled or Driven) <input type="checkbox"/> Surface (Identify) _____ <input type="checkbox"/> Roof Catchment <input type="checkbox"/> Other (Identify) _____ <input type="checkbox"/> Holding Tank		<input type="checkbox"/> Private <input type="checkbox"/> Public (Serves more than one family)		<input type="checkbox"/> None <input type="checkbox"/> Chlorination <input type="checkbox"/> Filtration <input type="checkbox"/> Mineral Removal <input type="checkbox"/> Other: _____
Well Data				
Is the Height of the Well Casing more than 12" above the Ground? <span style="float: right;"><input type="checkbox"/> Yes <input type="checkbox"/> No</span>				
Is a sanitary seal installed on the well casing? <span style="float: right;"><input type="checkbox"/> Yes <input type="checkbox"/> No</span>				
Is drainage directed away from or around the casing within a radius of 10 feet of the well casing? <span style="float: right;"><input type="checkbox"/> Yes <input type="checkbox"/> No</span>				
Date Drilled	Depth of Well (Feet)	Static Water Level (Feet)	Yield (if Available) <span style="float: right;">Gal/Min</span>	Pump Rate (if Available) <span style="float: right;">Gal/Min</span>
Separation Distances from the Well Casing to each of the Following Sources of Contamination:				
Septic/Holding Tank on Lot		Sewer Lines on Lot		Absorption Area on Lot
Closest Septic/Holding Tank on Adjacent Lot		Closest Sewer Lines on Adjacent Lot		Closest Edge of an Absorption Area on Adjacent Lot
If toxic materials are stored on the property, including fuel tanks, paints, lubricants and other petroleum based materials, pesticides, fungicides or herbicides, indicate distance from contaminants to well casing:			On Lot	On Adjacent Lot
Water Sample Taken by: Name			Sampler is:	
Address			<input type="checkbox"/> Buyer <input type="checkbox"/> Engineer <input type="checkbox"/> Banker <input type="checkbox"/> Government Official	
Water Sample Results: <input type="checkbox"/> Satisfactory - Date: _____ <input type="checkbox"/> Unsatisfactory - Date: _____				
Comments/Recommendations:				




Trench 30' x 5' E.D.

1,000 gal plastic  
2-comp. tank

2 BR septic system

1 BR cabin




Well

100'

RECEIVED  
AUG 15 1995  
DEPARTMENT OF  
ENVIRONMENTAL CONSERVATION  
MSDO  
PLAN VIEW

NTS



DEEP TRENCH SECTION


NTS

Lot 7 Block 7 Big Lake Hqts #1  
Wastewater Disposal System  
Record Drawing

ERDMAN & ASSOCIATES  
Consulting Engineers  
191 East Swanson Ave.  
Wasilla, Alaska 99654  
Phone 376-8989 Fax 373-2157

Project #95085 7/20/95


ERDMAN & ASSOCIATES  
 Engineering/Water Testing  
 191 E. Swanson Ave, #201  
 Wasilla, AK 99654



SOILS LOG — PERCOLATION TEST

PERFORMED FOR: BARBARA SHAW/MIKE ALEXANDER

LEGAL DESCRIPTION: LOT 7 BLOCK 7 BIGLAKE HEIGHTS # 1



**RECEIVED**  
 AUG 15 1995

DEPARTMENT OF ENVIRONMENTAL CONSERVATION  
 MSDCO

COMMENTS USE 150 FT<sup>2</sup> BEDROOM

PERFORMED BY: CHOLLER/E&A DATE: 5/18/95