




SURVEY DESCRIPTION

A parcel of land in Houston County, Alabama, and being more particularly described as follows; BEGINNING at a 5/8" iron pipe marking the southwest corner of the SW1/4 of the NE1/4 of Section 17, T3N, R25E, and thence N00°32'22"W 1269.29 feet to a 5/8" iron pipe on the south side of Hollis Dairy Road, thence along a curve to the right having a radius of 2120.00 feet and a chord bearing and distance of S85°22'54"E 187.01 feet to a 5/8" iron pipe, thence S82°51'12"E along the south side of said road 456.65 feet to a 5/8" iron pipe, thence S84°55'37"E along the south side of said road 717.91 feet to a 1/2" rebar, thence S16°14'37"E 1090.15 feet to a 5/8" iron pipe, thence N86°49'14"E 528.08 feet to a 1/2" rebar on the north R/W of Judge Logue Road, thence S67°39'15"W along said R/W 1955.47 feet to a 5/8" iron pipe, thence along a curve to the right having a radius of 2875.00 feet and a chord bearing and distance of S75°17'55"W 764.89 feet to a 5/8" iron pipe, thence S82°56'34"W along said R/W 867.09 feet to a 5/8" iron pipe,, thence N48°40'47"W 66.42 feet to a 5/8" iron pipe on the east R/W of South County Road No. 9, thence N00°18'10"W along said R/W 814.21 feet to a 5/8" iron pipe, thence N86°54'43"E 1290.20 feet to the point of beginning. Said parcel being in the S1/2 of the NE1/4, the N1/2 of the SE1/4 and the NE1/4 of the SW1/4 of Section 17, T3N, R25E, and containing 83.14 acres more or less.

SURVEY FOR: JERRY KING

TYPE OF SURVEY: LOAN-BOUNDARY SURVEY
SOURCE: AS REQUESTED

STATE OF ALABAMA
COUNTY OF: HOUSTON

LEGEND
ECM EXISTING CONCRETE MARKER
EIP EXISTING IRON PIPE
SIP SET 5/8" IRON PIPE
SCM SET 4"x4" CONCRETE MARKER
POC POINT OF COMMENCING
POB POINT OF BEGINNING
R/W RIGHT OF WAY
CH CHORD BEARING AND DISTANCE
FM FIELD MEASURED
D DEED CALL
P PLAT CALL
MBL MINIMUM BUILDING LINE
S/D SUBDIVISION
CONC CONCRETE
EF EXISTING FENCE
X X X

GENERAL NOTES:
ALL BEARINGS AND DISTANCES FIELD MEASURED OR CALCULATED FROM FIELD TRAVERS UNLESS NOTED. THIS SURVEY WAS PERFORMED FOR THE ABOVE NAMED, FOR THE SINGULAR PURPOSE OF OBTAINING A MORTGAGE. THIS SURVEY IS NOT INTED TO DELINEATE LOCAL AREAS OF PARTICULAR CONCERN, WETLANDS, FLOOD HAZARD AREAS OR ANY OTHER JURISDICTIONAL BOUNDARIES. THE SURVEYOR MAKES NO CLAIM AS TO SUBSURFACE FEATURES OTHER THAN AS SHOWN HEREON, AND ASSUMES NO LIABILITY

DATE OF SURVEY: WORK ORDER NO. 07174
THIS 10TH DAY OF AUGUST 2007 ACAD/07174
REVISED

ADDRESS:

HENRY JUDAH AND ASSOCIATES, INC.
2235 LONNIE WATSON ROAD
NEWTON, ALABAMA 36352
TEL: 334/299/3154

SURVEY NOTES:
THIS SKETCH IS THE PROPERTY OF HENRY JUDAH AND ASSOCIATES, INC. AND SHALL NOT BE REPRODUCED IN WHOLE OR PART WITHOUT WRITTEN PERMISSION OF THE UNDERSIGNED. ©

I STATE THAT A FIELD SURVEY OF THE PROPERTY SHOWN HEREON WAS MADE UNDER MY DIRECTION AND THAT THE SURVEY AND DRAWING MEET THE CURRENT REQUIREMENTS OF THE STANDARD OF PRACTICE FOR SURVEYING IN THE STATE OF ALABAMA. THE UNDERSIGNED HAS NOT BEEN PROVIDED A CURRENT TITLE OPINION OR ABSTRACT OF MATTERS AFFECTING THE TITLE OR BOUNDARY TO THE SUBJECT PROPERTY. IT IS POSSIBLE THERE ARE DEEDS OF RECORD, UNRECORDED DEEDS, EASEMENTS OR OTHER INSTRUMENTS WHICH COULD AFFECT THE BOUNDARY. NO WARRANTY OR GUARANTEE IS GIVEN OR IMPLIED AS TO OWNERSHIP.

BY: *Henry Judah*
REGISTERED LAND SURVEYOR NO. 20638
SURVEY CAP NO. CA 0086
REPRODUCTIONS OF THIS DRAWING ARE NOT VALID UNLESS SEALED WITH AN EMBOSSED SURVEYOR'S SEAL